

CITY OF BOARDMAN, OREGON

TABLE OF CONTENTS

SECTION 6

CONCRETE CURB AND GUTTER, CROSS GUTTERS, SIDEWALK, AND DRIVEWAY TRANSITIONS

PART 1 - General	6-1
1.1 Scope of Work	6-1
PART 2 - Materials.....	6-1
2.1 Concrete Characteristics.....	6-1
2.2 Portland Cement	6-2
2.3 Aggregates.....	6-2
2.4 Water	6-3
2.5 Admixtures	6-3
2.6 Pre-molded Joint Filler.....	6-4
2.7 Aggregate Base.....	6-4
2.8 Truncated Dome Detectable Warning Texture.....	6-4
PART 3 - Execution	6-4
3.1 Earthwork.....	6-4
3.2 Base Aggregate.....	6-4
3.3 Forms.....	6-5
3.4 General Placement and Finishing	6-5
3.5 Curing	6-6
3.6 Restrictions Due to Weather	6-6
3.7 Backfill	6-7
3.8 Curb and Curb and Gutter	6-8
3.9 Sidewalk and Driveway and Alley Approaches	6-10
3.10 Steps.....	6-11
3.11 Reinforcing Bars	6-12
3.12 Truncated Dome Detectable Warning Texture.....	6-12
3.13 ADA Requirements	6-12
3.14 Testing and Inspection.....	6-12

CITY OF BOARDMAN, OREGON

TECHNICAL SPECIFICATIONS

SECTION 6

CONCRETE CURB AND GUTTER, CROSS GUTTERS, SIDEWALK, AND DRIVEWAY TRANSITIONS

PART 1 - GENERAL

1.1 Scope of Work

- A. This Work shall consist of the construction of Portland Cement concrete curb, curb and gutter, sidewalk, steps, and driveway and alley approaches. They shall be constructed in accordance with these Technical Specifications and shall be in reasonably close conformity to the lines, grades, and dimensions established by the City.
- B. Concrete cross gutters shall be constructed to the same requirements as concrete curb and gutter and as detailed on the City Standard Drawings.
- C. Work shall conform with the general practices outlined in the American Concrete Institute publication "Slabs on Grade" and in accordance with applicable provisions of ACI Manual of Concrete Practices, Parts 1, 2, and 3 and "Standard Specifications for Ready Mixed Concrete" (ASTM C94) except as modified below.

PART 2 - MATERIALS

2.1 Concrete Characteristics

- A. The Portland Cement concrete used for this Work shall be a commercial transit mix. The exact proportions of all the materials entering into the concrete shall be as established by an approved laboratory mix design and shall be changed only as directed by the City or Laboratory when necessary to obtain the specified strength, desired density, uniformity, or workability. Previously prepared mix designs will be allowed provided adequate test data is available to document the suitability of the mix and the Contractor can document that the same materials are being used. The mix design shall be provided to the City for review.
- B. The concrete shall have the following characteristics.

CITY OF BOARDMAN, OREGON

TECHNICAL SPECIFICATIONS

SECTION 6

CONCRETE CURB AND GUTTER, CROSS GUTTERS, SIDEWALK, AND DRIVEWAY TRANSITIONS

Parameter	Value
Min. 28-day Compressive Strength	4,000 psi
Min. Cement per Cubic Yard	564 lbs./yd.
Max. Water-Cement Ratio	0.45
Air Content (range)	5-7 percent
Max. Allowable Slump	4 inches

- C. In some localities, additional cement may be required to achieve the minimum 4,000 psi 28-day compressive strength. The use of additives will be allowed when designed into the mix. Mixes used with reinforcing steel shall have a maximum water soluble chlorine ion content of 0.06 percent of mix design concrete weight.

2.2 Portland Cement

- A. Portland cement shall conform to the requirements of ASTM C150, for Type I - II cement.
- B. All cement shall be stored in a suitable weather-tight building in such a manner as to protect the cement from dampness and to permit easy access for proper inspection. Storage bins for bulk cement shall be weather-tight and constructed so there will be no dead storage.

2.3 Aggregates

- A. General

All aggregates for concrete shall conform to the requirements of ASTM C33.

Fine and coarse aggregates shall be stored and measured separately. Aggregates shall be protected from contamination with dust, dirt, or other foreign materials.

- B. Fine Aggregate

Fine aggregate shall consist of natural sand having hard, strong, and durable particles, which does not contain more than 2 percent by weight of such deleterious substances

CITY OF BOARDMAN, OREGON

TECHNICAL SPECIFICATIONS

SECTION 6

CONCRETE CURB AND GUTTER, CROSS GUTTERS, SIDEWALK, AND DRIVEWAY TRANSITIONS

as clay lumps, shale, schist, alkali, mica coated grains, or soft and flaky particles. The grading of fine aggregate shall range uniformly from coarse to fine within the limits indicated in ASTM C33.

C. Coarse Aggregate

1. Coarse aggregate shall consist of clean, hard, fine grained, sound crushed rock, or washed gravel that does not contain in excess of 5 percent by weight of flat, chip like, thin, elongated, friable, or laminated pieces, or more than 2 percent by weight of shale or cherty material.
2. Any piece having a major dimension in excess of 2-1/2 times the average thickness shall be considered to be flat and/or elongated.
3. The maximum size of coarse aggregate shall not exceed 1-1/2 inches or one-fifth of the narrowest dimension between the forms nor three-quarters of the clear spacing between reinforcing bars. The minimum size of coarse aggregate shall be 3/4-inch unless approved otherwise.
4. Coarse aggregate shall be uniformly graded from coarse to fine within the limits allowed in ASTM C33.

2.4 Water

Water for mixing shall be clean, fresh, and free from injurious amounts of oil, acid, chlorides, sulfates, alkali, organic matter, or other deleterious substances.

2.5 Admixtures

The use of admixtures will be allowed only when included in the mix design or as specified. Admixtures used will be considered a means of improving workability and/or placement of the concrete. Admixtures shall conform to requirements:

Parameter	Reference
Air-entraining	ASTM C260
Water Reducer	ASTM C494, Type A
Set Retarding	ASTM C494, Type B
Water Reducing/Set Retarding	ASTM C494, Type D

CITY OF BOARDMAN, OREGON

TECHNICAL SPECIFICATIONS

SECTION 6

CONCRETE CURB AND GUTTER, CROSS GUTTERS, SIDEWALK, AND DRIVEWAY TRANSITIONS

High Range Water Reducing (Superplasticizer)	ASTM C494, Type F and G
Pozzolanic	ASTM C618
Fly Ash	AASHTO M 295, Class C or F

2.6 Pre-molded Joint Filler

Pre-molded joint filler for use in expansion (through) joints shall be asphalt-impregnated cane fiber and shall conform to ASTM D1751. The thickness shall be 1/2-inch or match existing adjacent expansion joints.

2.7 Aggregate Base

The aggregate base used under any of the structures listed in this section of these Technical Specifications shall conform with the requirements of Section 640 of the Oregon Standard Specifications for Construction, 2002 edition, and shall be 3/4"-0 unless otherwise approved.

2.8 Truncated Dome Detectable Warning Texture

Truncated dome detectable warning texture used on sidewalk ramps shall be a material listed on the ODOT Qualified Products List as approved by ODOT for the intended use. See Oregon Standard Drawings RD900 series.

PART 3 - EXECUTION

3.1 Earthwork

Excavation shall be made to the required depths and to a width that will permit the installation and bracing of forms. All soft and unsuitable material shall be removed and replaced with suitable material. The top 6 inches of any cut section and the full depth of any embankment shall be compacted to a minimum of 90 percent of the maximum density as determined by ASTM D1557.

3.2 Base Aggregate

The base aggregate shall be placed as shown on the Drawings and shall be compacted to 90 percent of the maximum density as determined by ASTM D698.

CITY OF BOARDMAN, OREGON

TECHNICAL SPECIFICATIONS

SECTION 6

CONCRETE CURB AND GUTTER, CROSS GUTTERS, SIDEWALK, AND DRIVEWAY TRANSITIONS

3.3 Forms

Forms shall be wood or metal and shall extend for the full depth of the concrete. All forms shall be straight, free from ways, and of sufficient strength to resist the pressure of the concrete without springing. Bracing and staking of forms shall be such that the forms remain in both horizontal and vertical alignment until their removal.

3.4 General Placement and Finishing

- A. The foundation and forms shall be well wetted prior to placement of the concrete. Unless otherwise specified, all concrete shall be placed upon clean, damp surfaces free of running or standing water, and never upon soft mud, dry porous earth, or frozen subgrade.
- B. All concrete shall be placed before the initial set has occurred. It shall be placed within 1-1/2 hours after water has been added to the mix. The temperature of the concrete at placement shall not be below 50°F or exceed 90°F unless approved otherwise by the City.
- C. The concrete shall be placed on a moist base and deposited as close as possible to its final location and to its required depth. Movement of the concrete horizontally with a vibrator will not be allowed.
- D. Once the concrete has been placed, it shall be struck off to the proper elevation using a straightedge and sawing motion. A smooth surface shall be provided after the concrete has been straight edged by the use of a bull float or Darbie. A wooden bull float shall be used unless the Contractor can show that a magnesium bull float does not seal in the bleed water.
- E. Bull floating shall occur immediately after striking off and before bleed water accumulates on the surface. Bull floating shall be done in such a manner that the surface is not sealed, so bleed water is not trapped below the surface. Care shall be taken not to overwork the surface. The use of a jitterbug or tamper will not be allowed. Initial edging shall be performed with a wide edger, again in a manner that will avoid sealing the surface.
- F. Upon completion of the above floating, the concrete shall be allowed to sit until the bleeding has stopped, the bleed water has disappeared, and the concrete is firm enough to permit a man to walk on the surface leaving footprints no more than 1/4-inch deep.

CITY OF BOARDMAN, OREGON

TECHNICAL SPECIFICATIONS

SECTION 6

CONCRETE CURB AND GUTTER, CROSS GUTTERS, SIDEWALK, AND DRIVEWAY TRANSITIONS

After the waiting period, the concrete may be floated and finished as required. Adding water to the surface or working bleed water to aid in finishing is not allowed.

3.5 Curing

- A. As soon as the concrete has been placed and finished, as specified, it shall be cured:
 - 1. By application of an approved Type 2, Class B white or gray pigmented or Type 1-D clear compound with fugitive dye liquid membrane-forming compound applied uniformly at a rate of at least 1 gallon per 200 square feet to the damp concrete by pressure spray methods; or
 - 2. By keeping the concrete continually damp for at least 120 hours. The actual curing method and materials shall meet the requirements of ACI 308 and ASTM C309.
- B. The Contractor shall protect the newly placed concrete from vandalism and any other damages. The exact method of protection shall be left up to the Contractor. Any damages, regardless of the cause, shall be repaired or replaced to the satisfaction of the City.

3.6 Restrictions Due to Weather

- A. Cold Weather
 - 1. Concrete placement in cold weather (50°F or less) shall conform to "Recommended Practice for Cold Weather Concreting" (ACI 306).
 - 2. Salts, chemicals, or other foreign materials shall not be mixed with the concrete to prevent freezing.
 - 3. All concrete shall be effectively protected from frost action for a period of five days after placement. Upon written notice from the City, all concrete that may have become damaged by frost action shall be replaced by the Contractor at their own expense.

CITY OF BOARDMAN, OREGON

TECHNICAL SPECIFICATIONS

SECTION 6

CONCRETE CURB AND GUTTER, CROSS GUTTERS, SIDEWALK, AND DRIVEWAY TRANSITIONS

B. Hot Weather

1. For concrete placed during extremely hot weather (air temperature exceeding 95°F), the aggregate shall be cooled by frequent spraying in such a manner as to utilize the cooling effect of evaporation.
2. During such periods, the placement schedule shall be arranged, as approved, in such a manner as to provide time for the temperature of the previously placed concrete to begin to recede.
3. The mixing water shall be the coolest available at the Site insofar as is practical.

C. Low Humidity/Wind

1. Pouring of concrete during periods of low humidity (below 50 percent) and/or windy conditions should be avoided when feasible and economically possible, particularly when large surface areas need to be finished.
2. No concrete shall be placed if the rate of evaporation approaches 0.2 pounds per square foot per hour unless precautions against plastic shrinkage cracking are taken.
3. In any event, surfaces exposed to the drying wind shall be covered up immediately after finishing with polyethylene sheets and be water cured continuously as soon as the concrete has set up. Curing compounds, in lieu of water, may not be used.

3.7 Backfill

- A. After the concrete has reached sufficient strength, the space in back of structures shall be backfilled to the required elevation with the proper material as specified, which shall be compacted until firm and solid.
- B. When the entire Project has been finished, any damaged structure sections shall be repaired or replaced at no additional cost to the City.

CITY OF BOARDMAN, OREGON

TECHNICAL SPECIFICATIONS

SECTION 6

CONCRETE CURB AND GUTTER, CROSS GUTTERS, SIDEWALK, AND DRIVEWAY TRANSITIONS

3.8 Curb and Curb and Gutter

A. General

1. Concrete curb and curb and gutter shall be constructed in accordance with these Technical Specifications to the required lines, grades, and cross sections. They can be constructed with forms or with a curbing machine meeting the requirements of these Technical Specifications.
2. Curbs located on vertical or horizontal curves shall be constructed to result in a smooth curve.

B. Curbing Machine

1. The machine for extruding Portland Cement concrete curb shall be of the self-propelled type equipped with a material hopper, distributing screw, and adjustable curb forming devices capable of placing and compacting Portland Cement concrete to the lines, grades, and cross sections as shown in an even, homogeneous manner.
2. A grade line gauge or pointer shall be attached to the machine in such a manner that a continual comparison can be made between the curb being placed and the established curb grade as indicated by the offset guideline.

C. Placement and Finishing

1. The top and face of finished curb and curb and gutter shall be true and straight, and the top surface of curb shall be of uniform width free from humps, sags, honeycombs, or other irregularities.
2. When a straightedge 6 feet long is laid on the top face of the curb or on the surface of the gutter, the surface shall not vary more than 0.02 feet from the edge of the straightedge except at grade changes or vertical curves.
3. The Contractor shall construct all curb and gutter within 0.02 feet of true line, within 0.02 feet of established surface grade, cross section, and slope, and within 0.02 feet of specified thickness.
4. When the curbing machine is used, the Contractor shall feed the concrete into the extruding machine at a uniform rate and operate the machine under

CITY OF BOARDMAN, OREGON

TECHNICAL SPECIFICATIONS

SECTION 6

CONCRETE CURB AND GUTTER, CROSS GUTTERS, SIDEWALK, AND DRIVEWAY TRANSITIONS

sufficient restraint in a forward motion to produce a well compacted mass of concrete.

5. All exposed surfaces of the curb or curb and gutter shall be floated, followed by a light brush finish.
6. If forms are used, they shall be removed after the concrete has taken its initial set and while the concrete is still green enough to finish.
7. Minor defects shall be repaired with mortar containing one part Portland Cement and two parts sand. Honeycombed, slumped, and other structurally defective concrete shall be removed and replaced at no expense to the City.
8. All exposed formed surfaces shall receive a rubbed finish utilizing a Carborundum brick or other abrasive until a uniform color and texture is produced.

D. Joints

1. Expansion Joints

- a. Expansion joints shall be provided opposite abutting expansion joints, at the end of curved sections, at connections to existing curbs, and adjacent to any structure.
- b. The width of joints and thicknesses of filler shall match those of the joints and abutting or underlying concrete; elsewhere the filler thickness shall be 1/2 inch.
- c. Each expansion joint shall be at right angles to the structure alignment, vertical to the structure surface, placed full depth of the concrete section, and shall fully separate the concrete section.

2. Transverse Contraction Joints

- a. Transverse contraction joints of the weakened plane or dummy type shall be formed in the exposed surfaces opposite contraction joints in abutting Portland Cement concrete and at other locations in the new curb as required to confine the contraction joint spacing to a maximum of 10 feet. The joints shall be formed by grooving, by insertion and removal

CITY OF BOARDMAN, OREGON

TECHNICAL SPECIFICATIONS

SECTION 6

CONCRETE CURB AND GUTTER, CROSS GUTTERS, SIDEWALK, AND DRIVEWAY TRANSITIONS

of plates or other devices, by insertion and leaving in place of preformed bituminous filler, or by sawing.

- b. Contraction joints shall be 3/16-inch in width and a minimum depth of one-quarter of the thickness of the concrete. The edges of joints shall be tooled, unfilled grooves, and shall be clean and neat. Joint filler shall be even and flush with the surface of the concrete.
- c. If the joints are constructed by sawing, the sawing shall be performed as soon as practical after pouring and prior to the occurrence of any shrinkage cracking.

3.9 Sidewalk and Driveway and Alley Approaches

A. General

Concrete sidewalks shall be constructed in accordance with these Technical Specifications to the required lines, grades, and cross sections.

B. Placement and Finishing

- 1. Before the concrete is given the final finishing, the surface of the sidewalk shall be checked with a 10-foot straightedge; any irregularities of more than 1/4-inch in 10 feet shall be eliminated.
- 2. Edges, including those of expansion joints, shall be rounded with an approved finishing tool.
- 3. The final surface of the concrete shall receive a medium to coarse cross brooming finish so as to provide a granular or matte texture that will not be slick when wet.
- 4. Cross brooming shall be transverse to the length of the sidewalk and approaches.

CITY OF BOARDMAN, OREGON

TECHNICAL SPECIFICATIONS

SECTION 6

CONCRETE CURB AND GUTTER, CROSS GUTTERS, SIDEWALK, AND DRIVEWAY TRANSITIONS

C. Joints

1. Expansion Joints

- a. Expansion joints shall be provided opposite abutting expansion joints, at the end of curved sections, at all corners other than those 90 degrees, at connections to existing sidewalks, and adjacent to any structure.
- b. The width of the joints and thickness of the filler shall match those of the joints and abutting or underlying concrete; elsewhere, the thickness shall be 1/2 inch.
- c. Each expansion joint shall be at right angles to the structure alignment, vertical to the structure surface, placed full depth of the concrete section, and shall fully separate the concrete section.

2. Transverse Contraction Joints

- a. Transverse contraction joints are required every 5 feet along the length of sidewalks.
- b. The joints between sections shall be formed by steel templates 1/8-inch in thickness or sawn in with a concrete saw after initial set of the concrete to a minimum depth of 1/4 the thickness of the concrete. Joints shall be at right angles to the alignment.

3.10 Steps

A. General

Steps shall be constructed in accordance with these Technical Specifications to the required lines, grades, and cross sections.

B. Placement and Finishing

1. All edges shall be rounded with an approved finishing tool. All horizontal surface of the step shall receive burlap or cross-brooming finish to provide a granular or matte texture which will not be slick when wet.
2. After the forms are removed and while the concrete is still green, the vertical surfaces shall be finished.

CITY OF BOARDMAN, OREGON

TECHNICAL SPECIFICATIONS

SECTION 6

CONCRETE CURB AND GUTTER, CROSS GUTTERS, SIDEWALK, AND DRIVEWAY TRANSITIONS

3. Minor defects shall be repaired with a mortar containing one part Portland Cement and two parts sand. Honeycombed, slumped, and other structurally defective concrete shall be removed and replaced at no expense to the City.
4. All vertical surfaces shall receive a rubbed finish utilizing a Carborundum brick or other abrasive until a uniform color and texture is produced.

3.11 Reinforcing Bars

- A. Mild steel reinforcing bars shall be furnished, cut, bent, and placed as indicated on the Drawings and to the latest methods of practice approved by the Concrete Reinforcing Steel Institute.
- B. At the time of placing concrete, all reinforcement shall be free from loose mill scale, rust, grease, or other coating that might destroy or reduce its bond with concrete. Steel reinforcement not placed in the Work shall be stored under cover to prevent rusting and shall be placed on blocking so no steel touches any ground surfaces.
- C. Reinforcing steel shall be in position before concrete placement is begun. All reinforcing steel shall be tied together and supported in such a manner that displacement during placing of concrete will not occur.

3.12 Truncated Dome Detectable Warning Texture

Truncated dome detectable warning texture shall be installed in accordance with the manufacturer's requirements and in accordance with Oregon Standard Drawings RD900 series.

3.13 ADA Requirements

All sidewalks, curb ramps, etc., shall be constructed in accordance with all ADA standards and requirements. The Contractor shall immediately notify the City if non-ADA work is being required or being performed.

3.14 Testing and Inspection

The Contractor shall provide and maintain a quality control program that will ensure the quality of the Work and materials incorporated into the Project. See the Quality Control section of the General Requirements.

END OF SECTION